

Beach Electric, LLC
 PO Box 17462
 Seattle, WA 98127-1162

Time & Material Breakdown

Name / Address
Pike Place Market PDA 85 Pike Street, Room 500 Seattle, WA 98101 Attn: Accounts Payable

Date	Invoice #
1/21/2026	Estimate

		Project	
		25-247 Senior Center_Compressors	
Description	Qty	Rate	Total
<p>For the cooler/freezer replacement at the Pike Place Senior Center. Includes:</p> <p>Demo some of what is feeding the existing compressor(s) and use existing 30 amp circuit to feed two new disconnects. Make connection between the new disconnects and the two new compressors.</p> <p>Demo electrical at existing walk-in box and provide lighting. At the cooler box, using existing circuits, we will connect the air unit, thermostat (PB) and solenoid (PIBO). Assume air defrost. At the freezer box, using existing circuits, we will connect door/vent heat, connect defrost time clock to liquid solenoid (PIBO), thermostat (PBO), fans and defrost heat. We will provide duct seal at penetrations and insulate conduits for two feet (if practical). Total - Does not include sales tax.</p>		11,270.00	11,270.00
		Subtotal	\$11,270.00
		Sales Tax (10.35%)	\$0.00
		Total	\$11,270.00